BRUHAT BENGALURU MAHANAGARA PALIKE

TENDER DOCUMENT – KW4

(WORKS COSTING MORE THAN Rs. 100 LAKHS)

Name of Work: - CONSTRUCTION OF ADDITIONAL CLASS ROOMS AND COMPOUND WALL AT GOVT HIGHER PRIMARY SCHOOL(BANGLA SCHOOL)AT YELAHANKA OLD TOWN IN KEMPEGOWDA WARD NO.01

Estimate Cost: 300.00 Lakhs

Executive Engineer
Yelahanka, Division

BRUHAT BENGALURU MAHANAGARA PALIKE

No: BBMP/EE/YNK.D/E-PMT/05/ 2020-21

Office of the Executive Engineer
Yelahanka division, Bangalore – 560064
Dated : **03-9-2020**

INVITATION FOR TENDER (IFT)
(Short term- Tender Notification)
(Two Cover System)
(Through **GOK e–Procurement Portal** only)

1. The Executive Engineer Yelahanka Division invites tenders on behalf of the commissioner, BBMP, Bengaluru from eligible Tenderers for the construction of works detailed in the table below. The tenderers may submit tenders for works given in the table through e-procurement portal of the Government of Karnataka (viz https://eproc.karnataka.gov.in).The Tenderers are advised to note the minimum qualification criteria specified in Clause 3 of the Instructions to Tenderers to qualify for award of the contract **as per standard tender document KW-3 and KW-4.**
2. Tenders must be accompanied by Earnest Money Deposit specified for the work in the table below. Earnest money deposit will have to be in any one of the forms as specified in the Tender document (Minimum of Rs1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance by bank guarantee issued by Nationalized / Scheduled Bank and shall have to be valid for 180 days beyond the validity of the tender)
3. Tenders must be submitted online through e-procurement portal on or before 16.00 hours on **19-09-2020** and the opening of tenders will be as per the e-procurement portal guidelines.
4. GST Shall be Paid to the tendered amount separately
5. Other details can be seen in the tender documents.

Sl. No.	Name of the Work	Est. Cost	EMD (Rs. in Lakhs)	Cost of Tender form in Rs. (Non-Refundable)	Period of Completion
1	Construction of additional class rooms and compound wall at Govt. Higher primary school (Bangala school) at Yelahanka old town in Kempegowda ward no:01	300.00	4.50	As per e-Procurement Portal	09 Months (including monsoon)
2	Development of roads and drains at Maruthinagara 4th main and cross roads Basaveshwaranagara and Shivanahalli surrounding areas in ward no:01 of Yelahanka division (Package no-7)	400.00	6.00	As per e-Procurement Portal	06 Months (including monsoon)

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

3	Improvements to roads and drains at Kalli bhavi road and surrounding areas in ward no:01 of Yelahanka sub division	100.00	2.00	As per e-Procurement Portal	03 Months
4	Developments of roads and drains at Venkatala, Kenchenahalli, Nagenahalli, Harohalli village and Drilling of borewells and providing pipe line at SC/ST areas in ward no:01 and 02 of Yelahanka Division (Package no:08)	500.00	7.50	As per e-Procurement Portal	06 Months (including monsoon)
5	Comprehensive development of Chowdeshwari layout and surrounding areas in Chowdeshwari ward no:02	100.00	2.00	As per e-Procurement Portal	03 Months
6	Providing energy efficient LED Street lights Control Switches and wire to Main roads and around Chowdeshwari ward no:02	75.00	1.50	As per e-Procurement Portal	03 Months
7	Improvements to roads and drains at SC/ST areas in ward no:02 of Yelahanka sub division	100.00	2.00	As per e-Procurement Portal	03 Months
8	Improvements to Asphalting to roads and drains at Best county , Ambabhvaninagara , Ambabhavani layout , Prakruthi layout and surrounding areas in Attur ward no:03 of Yelahanka division (Package-06)	600.00	9.00	As per e-Procurement Portal	06 Months (including monsoon)
9	Providing energy efficient LED Street lights Control Switches and wire to Main roads and around Attur ward no:03	125.00	1.875	As per e-Procurement Portal	03 Months
10	Improvements to roads and drains at Vishwanagara in ward no:03 of Yelahanka Satellite town sub division	100.00	2.00	As per e-Procurement Portal	03 Months
11	Improvements to roads and drains at Bettahalli Colony in ward no:03 of Yelahanka satellite town sub division	100.00	2.00	As per e-Procurement Portal	03 Months
12	Construction of CC roads in 4th phase and surrounding areas in ward no-3	100.00	2.00	As per e-Procurement Portal	03 Months
13	Developments of roads and drains at Attur, Ananthapura, 3rd phase Sanitary core areas and Drilling of borewells and providing pipe line at SC/ST areas in ward no:03 and 04 of Yelahanka Division (Package no:09)	500.00	7.50	As per e-Procurement Portal	06 Months (including monsoon)
14	Providing multi colour shade lights at parks in ward no:03 and 04 of Yelahanka satellite town sub division	75.00	1.50	As per e-Procurement Portal	03 Months
15	Improvements to roads and drains at GKVK layout and Narayanappa layout in ward no:04	99.99	2.00	As per e-Procurement Portal	03 Months

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

16	Improvements to roads and drains at Allalasandra village in ward no:04 of Yelahanka satellite town sub division	75.00	1.50	As per e-Procurement Portal	03 Months
17	Improvements to roads and drains balance main and cross roads of Mathru layout in ward no:04	99.00	1.98	As per e-Procurement Portal	03 Months
18	Improvements to roads and drains in Chikkabommasandra Main and Cross roads in ward no:04	99.00	1.98	As per e-Procurement Portal	03 Months
19	Improvements to roads and drains at 4th A cross and 1st B Main and surrounding areas of B Sector in ward no:04	200.00	3.00	As per e-Procurement Portal	04 Months
20	Improvements to roads and drains at Ambedkarnagara and Kanakanagara areas in ward no:04 of Yelahanka satellite town sub division	125.00	1.875	As per e-Procurement Portal	03 Months
21	Improvements to roads and drains at 12th B main and surrounding areas of B sector in ward no:04	99.99	2.00	As per e-Procurement Portal	03 Months
22	Improvements to roads and drains at Main and Cross roads of Sharadanaga and Mathru layout in ward no:04	99.99	2.00	As per e-Procurement Portal	03 Months
23	Construction of RCC drain at 7th Cross 28th Cross, 29th Cross and 22nd A Main and surrounding areas in ward no:04	100.00	2.00	As per e-Procurement Portal	03 Months
24	Improvements to roads and drains at Allalasandra and Construction of CC road at Sanitary core in ward no:04	99.99	2.00	As per e-Procurement Portal	03 Months

NOTE:

1. Pre bid meeting will be held on **14-09-2020** at 15.00 hours in the office of the Executive Engineer (Yelahanka Division) to clarify the issue and to answer questions on any matter that may be raised at that stage as stated in "Instructions to Bidders" of the bidding document.
2. Technical Bids will be opened on the website https://eproc.karnataka.gov.in in the office of the Executive Engineer -Yelahanka Division on **21-09-2020** at **16.00** hours.
3. Aspiring Bidders/Contractors who have not registered in e-procurement should register before participating through the website https://eproc.karnataka.gov.in
4. Before submission of online bids, bidders must ensure that scanned copies of all the necessary documents have been attached with bid.
5. All the required information required for Bids must be filled and submit online.
6. For details, registration and e-payment visit GOK e-Procurement website https://eproc.karnataka.gov.in or contact e-Procurement Helpdesk at 080 – 22371090, 22340060, 22340948
7. This tender notice can also be seen on the BBMP website www.bbmp.gov.in

Sd/-
Executive Engineer
Yelahanka Division
Bruhat Bengaluru Mahanagara Palike

Copy submitted to:-
CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

1. Personnel Secretary to Worshipful Mayor to bring to the kind notice of the Worshipful Mayor.
2. Personnel assistant to Deputy mayor to bring to the notice of Deputy Mayor
3. The Commissioner, BBMP for kind information.
4. Special Commissioner (Projects)/Additional Commissioner(Projects) for kind information
5. Engineer – in – Chief, BBMP for kind information.
6. Council Secretary to bring to notice of the Standing Committee (Major Works).
7. The Chief Engineer / yelahanka zone / (Road Infrastructure)/Environment/Markets/ South zone/ West zone/ East zone/Rajarajeshwari Nagar zone / Bommanahalli zone/ Dasarahalli zone/ Yelahanka zone/ Mahadevapura zone/ (SWD) for kind information.
8. The Superintending Engineer, yelahanka zone / (Road Infrastructure)/ South/East/West/ Rajarajeshwari Nagar/ Bommanahalli / Dasarahalli/ Mahadevapura Zone for kind information.
9. Directorate General of Commercial Intelligence and Statistics, 565, Anandapur, Ward No.-108, Plot No.-22, Sector-1, Kolkata-700107, India, for kind information with a request to publish the same in the Indian Trade Journal.
10. The Joint Secretary(UDD) and the State Tender Bulletin Officer for kind information with a request to publish the same in the State Tender Bulletin
11. CAO / Chief Auditor for kind information.
12. IT Advisor with a Request to publish the same in the BBMP Website.
13. All Executive Engineers with a Request to publish the same in the Display /Notice Boards.
14. ACF (Yelahanka) / Accounts Superintendent / Cashier for information for necessary action.
15. Public Relation Officer, BBMP for information and to publish in two leading National Newspapers in Kannada and English.
16. Notice board Office Copy.

Executive Engineer
Yelahanka Division
Bruhat Bangalore Mahanagara Palike

SECTION 2: INSTRUCTIONS TO TENDERERS (ITT)

Table of Clauses

		Page No.
A.	**General**	
1.	Scope of Tender	8
2.	Eligible Tenderers	8
3.	Qualification of the Tenderer	8
4.	One Tender per Tenderer	10
5.	Cost of Tendering	10
6.	Site Visit	10
B.	**Tender Documents**	
7.	Content of Tender documents	10
8.	Clarification of Tender Document	10
9.	Amendment of Tender documents	10
C.	**Preparation of Tenders**	
10.	Documents comprising the Tender	11
11.	Tender prices	11
12.	Tender validity	11
13.	Earnest money deposit	11
14.	Format and signing of Tender	12
D.	**Submission of Tenders**	
15.	Sealing and marking of Tenders	12
16.	Deadline for submission of Tenders	13
17.	Late Tenders	13
18.	Modification and Withdrawal of Tenders	13
E.	**Tender opening and evaluation**	
19.	Opening of First Cover of all Tenders and evaluation to determine Qualified Tenderers	14
20.	Opening of Second Cover Tenders of qualified Tenders and evaluation	14
21.	Process to be confidential	14
22.	Clarification of Tenders	15
23.	Examination of Tenders and determination of responsiveness	15
24.	Correction of errors	15
25.	Evaluation and comparison of Tenders	15
F.	**Award of contract**	
26.	Award criteria	16
27.	Employer's right to accept any Tender and to reject any or all Tenders	16
28.	Notification of award and signing of Agreement	16
29.	Security deposit	16
30.	Advance payment and Security	17
31	Corrupt or Fraudulent Practices	17

A. General

1. Scope of Tender

1.1 **The Executive Engineer, Yelahanka Division, BBMP** (Referred to as Employer in these documents) invites tenders following Two Cover tender procedure, from eligible Tenderers, for the construction of works (as defined in these documents and referred to as "the works") detailed in the Table given in the Invitation for Tenders (IFT). The Tenderers may submit tenders for any or all of the works detailed in the table given in IFT.

3.5 Sub-contractors' experience and resources shall not be taken into account in determining the Tenderer's compliance with the qualifying criteria except to the extent stated in 3.2 (d) and (e) above.

3.6 Tenderers who meet the above specified minimum qualifying criteria, will only be qualified, if their available tender capacity is more than the total tender value. The available tender capacity will be calculated as under:

Assessed available tender capacity = (A*N*1.5 - B)

Where

A = Maximum value of civil engineering works executed in any one year during the last five years *(updated to* ***2019-2020*** *price level)* taking into account the completed as well as works in progress.

N = Number of years prescribed for completion of the works for which tenders are invited.

B = Value, at **2019-2020** price level, of existing commitments and on-going works to be completed during the next **06 months**

Note: ***The statements showing the value of existing commitments and on-going works as well as the stipulated period of completion remaining for each of the works listed should be countersigned by the Employer in charge, not below the rank of an Executive Engineer or equivalent.***

3.7 Even though the Tenderers meet the above criteria, they are subject to be disqualified if they have:

- made misleading or false representations in the forms, statements and attachments submitted in proof of the qualification requirements; and/or
- Record of poor performance such as abandoning the works, not properly completing the contract, inordinate delays in completion, litigation history, or financial failures etc.; and/or
- participated in the previous Tender for the same work and had quoted unreasonably high tender prices and could not furnish rational justification.

4. One Tender per Tenderer:

4.1 Each tenderer shall submit only one tender for one package. A tenderer who submits or participates in more than one Tender (other than as a sub-contractor or in cases of alternatives that have been permitted or requested) will cause all the proposals with the Tenderer's participation to be disqualified.

5. Cost of Tendering:

5.1 The tenderer shall bear all costs associated with the preparation and submission of his tender, and the Employer will in no case be responsible and liable for those costs.

6. Site visit:

6.1 The Tenderer at his own responsibility and risk is encouraged to visit and examine the Site of Works and its surroundings and obtain all information that may be necessary for preparing the Tender and entering into a contract for construction of the Works. The cost of visiting the Site shall be at the Tenderer's own expense.

B. Tender documents

7. Content of Tender documents

7.1 The set of tender documents shall have all the Sections given in Page 2:

7.2 Both the sets should be completed and returned with the tender.

8. Clarification of Tender Documents

8.1 A prospective tenderer requiring any clarification of the tender documents may notify the Employer in writing or by cable (hereinafter "cable" includes telex and facsimile) at the Employer's address indicated in the invitation to tender. The Employer will respond to any request for clarification which he receives earlier than 15 days prior to the deadline for submission of tenders. Copies of the Employer's response will be forwarded to all purchasers of the tender documents, including a description of the enquiry but without identifying its source.

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

12.1 Tenders shall remain valid for a period not less than one hundred eighty (180) days after the deadline date for tender submission specified in Clause 16. A tender valid for a shorter period shall be rejected by the Employer as non-responsive.

12.2 In exceptional circumstances, prior to expiry of the original time limit, the Employer may request that the Tenderers may extend the period of validity for a specified additional period. The request and the Tenderers' responses shall be made in writing or by cable. A Tenderer may refuse the request without forfeiting his earnest money deposit. A Tenderer agreeing to the request will not be required or permitted to modify his tender, but will be required to extend the validity of his earnest money deposit for a period of the extension, and in compliance with Clause 13 in all respects.

13. Earnest money deposit

13.1 The Tenderer shall furnish, as part of his tender, earnest money deposit (EMD) at the following rates

a) upto Rs.20 Lakhs - 2.5%
b) Rs.20 Lakhs and above upto Rs. 1 crore – 2% subject to a minimum of Rs. 50,000/-
c) Rs.1 crore and above up to Rs.10 crores – 1.5% subject to a minimum of Rs. 2,00,000/-
d) Rs.10 crores and above – 1% subject to a minimum of Rs.15,00,000/-.
e) Fixed Deposit Receipt (FDR) subject to the following condition

- Maturity date of FDRs issued by the Bank should be beyond the date expected date of finalization of the tender.

Earnest money deposit will have to be in any one of the forms as specified in the Tender document and as per circular PWD:15:ITC:2008/2009 Dated:02-12-2010 (Minimum of Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance by bank guarantee/FDR issued by Nationalized/Scheduled Bank and shall have to be valid for 90 days beyond the validity of the tender.

As per Circular: PWD:15:ITC:2008/2009 Dated:02-12-2010 the Tenderer shall submit the ORIGINAL BG/FDR for Part EMD on or before the Opening of Technical Bid, if failed to submit, the bid will be rejected and the initial amount deposited through e-procurement will be forfeited and further their names will be proposed for Black Listing if resorted repeatedly.

13.2 Instruments having fixed validity issued as earnest money deposit for the tender shall be valid for 45 days beyond the validity of the tender.

13.3 Any tender not accompanied by an acceptable earnest money deposit and not secured as indicated in Sub-Clauses 13.1 and 13.2 above shall be rejected by the Employer as non-responsive.

13.4 The earnest money deposit of unsuccessful Tenderers will be returned within 30 days of the end of the tender validity period specified in Sub-Clause 12.1.

13.5 The earnest money deposit of the successful Tenderer will be discharged when the Tenderer has signed the Agreement and furnished the required Performance Security.

13.6 The earnest money deposit may be forfeited:

(a) if the Tenderer withdraws the Tender after tender opening during the period of tender validity;
(b) if the Tenderer does not accept the correction of the Tender Price, pursuant to Clause 24; or
(c) in the case of a successful Tenderer, if the Tenderer fails within the specified time limit to
  (i) Sign the Agreement; or
  (ii) Furnish the required Security deposit

14. Format and signing of Tender

14.1 The Tenderer shall prepare one original and a copy of the documents comprising the Tender as described in Clause 10 of these *Instructions to Tenderers*, and clearly marked "**ORIGINAL**" and "**COPY**" as appropriate. In the event of discrepancy between them, the original shall prevail.

14.2 The original and a copy of the Tender shall be typed or written in indelible ink and shall be signed by a person or persons duly authorized to sign on behalf of the Tenderer. All pages of the tender where entries or amendments have been made shall be initialed by the person signing the tender

14.3 The Tender shall contain no alterations or additions, except those to comply with instructions issued by the Employer, or as necessary to correct errors made by the Tenderer, in which case such corrections shall be initialed by the person signing the Tender.

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

18.3 No Tender may be modified after the deadline for submission of Tenders.

18.4 Withdrawal or modification of a Tender between the deadline for submission of Tenders and the expiration of the original period of Tender validity specified in Clause 12.1 above or as extended pursuant to Clause 12.2 may result in the forfeiture of the earnest money deposit pursuant to Clause 13.

18.5 Tenderers may only offer discounts to, or otherwise modify the prices of their Tenders by submitting Tender modifications in accordance with this clause, or included in the original Tender submission.

E. Tender opening and evaluation

19. Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers:

19.1 The Employer will open the First Covers of all the Tenders received (except those received late or withdrawn), including modifications for First Cover made pursuant to Clause 18, in the presence of the Tenderers or their representatives who choose to attend on **21-09-2020 at 16.00 hours** on the date and the place specified in Clause 16. In the event of the specified date of Tender opening being declared a holiday for the Employer, the Tenders will be opened at the appointed time and location on the next working day.

19.2 Envelopes marked "**WITHDRAWAL**" shall be opened and read out first. The First Cover of Tenders for which an acceptable notice of withdrawal has been submitted pursuant to Clause 18 shall not be opened.

19.3 The Tenderers names, the presence or absence of earnest money deposit (amount, format and validity), the submission of qualification information and such other information as the Employer may consider appropriate will be announced by the Employer at the opening. Late and withdrawn Tenders will be returned unopened to tenders.

19.4 The Employer shall prepare minutes of the Tender opening, including the information disclosed to those present in accordance with Sub-Clause 19.3.

19.5 The Second Cover of all the Tenderers including modifications for Second Cover shall be placed in a large cover and securely sealed in the presence of the tenderers or their representatives, who are present and also get the same signed by all those tenderers or their representatives. The large cover shall be kept in safe custody by the Employer.[4]

19.6 The Employer will evaluate and determine whether each tender (a) meets the eligibility criteria defined in ITT Clause 2; (b) is accompanied by the required earnest money deposit as per stipulations in ITT Clause and (c) meets the minimum qualification criteria stipulated in ITT Clause 3. The Employer will draw out a list of qualified Tenderers.[5]

20.1 The Employer will inform all the Qualified Tenderers the time, date and venue fixed for the opening of the Second Cover containing the priced Tenders. The Employer will open the Second Covers of Qualified Tenderers at the appointed time and date in the presence of the Tenders or their representatives who choose to attend. In the event of the specified date of Second Cover opening being declared a holiday for the Employer, the Second Covers will be opened at the appointed time and location on the next working day.

20.2 Envelopes marked **"MODIFICATION FOR SECOND COVER"** shall be opened and the submissions therein read out in appropriate detail.

20.3 The Tenderers' names, the Tender prices, the total amount of each Tender, any discounts, Tender modifications and withdrawals, and such other details as the Employer may consider appropriate, will be announced by the Employer at the opening. No Tender shall be rejected at Tender opening.

20.4 The Employer shall prepare minutes of the Second Cover Tender opening, including the information disclosed to those present in accordance with Sub-Clause 20.3.

21. Process to be confidential

---

[4] **Refer GOK circular No. PWD 1359 SO/FC 2001 (P-2) dated 30th June 2003.**

[5] The evaluation of the technical aspects contained in the first cover should be completed within a reasonable period and the time gap between the opening of the first and second cover should be the minimum and in any case not more than 45 days {In exceptional cases, approval of the Secretary to the Government of the concerned Department/Managing Director of the Corporation shall be obtained where the period is more than 45 days but less than 60 days. If it exceeds 60 days the tenders shall be reinvited.

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

2016-17						
2017-18						
2018-19						
2019-20						

1.5 Information on works for which Tenders have been submitted and works which are yet to be completed as on the date of this Tender.

(A) <u>Existing commitments and on-going works:</u>

Description of Work	Place & State	Contract No. & Date	Name And Address of Employer	Value of Contract (Rs. lakhs)	Stipulated period of completion	Value of works remaining to be completed (Rs. lakhs) Attach Certificates from Engineers –in-Charge	Anticipated date of completion
1	2	3	4	5	6	7	8

(B) <u>Works for which Tenders already submitted:</u>

Description of Work	Place & State	Name and Address of Employer	Estimated value of works (Rs. lakhs)	Stipulated period of completion	Date when decision is expected	Remarks if any
1	2	3	4	5	6	7

1.6. The following items of equipment are considered essential for successfully carrying out the works. The Tenderer should furnish all the information listed below.

Item of Equipment	Requirement[8]		Owned	Owned and available		
	No.	Capacity		Number/ Capacity	Age/ condition	Remarks

1.7 Reports on the financial standing of the tenderer, such as profit and loss statements and auditor's reports for the last five years;

1.8 Qualification and experience of the key technical and management personnel in permanent employment with the tenderer and those that are proposed to be deployed on this contract, if awarded.

1.9. Name, address, and telephone, telex, and fax numbers of the Tenderers' bankers who may provide references if contacted by the Employer.

1.10 Evidence of access to financial resources to meet the qualification requirement specified in ITT Clause3.3 (b): Cash in hand, Letter of Credit etc. List them below and attach certificate from the Banker in the suggested format as under:

BANKER'S CERTIFICATE

This is to certify that M/s. .... is a reputed company with a good financial standing. If the contract for this work, namely .... (*name of the work*) is awarded to the above firm, we shall be able to provide overdraft/credit facilities to the extent of Rs. .... to meet the working capital requirements for executing the above contract

Name of the Bank, Senior Bank Manger
with Signature
Address:................................

1.11 Proposals for subcontracting components of works amounting to more than 20% of the contract price.

Item of Work	Value of Sub-Contract	Identified Sub-Contractor (Name and address)	Experience of similar work (Attach certificates from the respective Employers.)
1	2	3	4

[8] The item of equipment, required number and capacity should match with those specified in ITT Clause 3.3 (a)

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

Letter of Acceptance

<u>(letterhead paper of the Employer)</u> ……………….[date]

To:

………………………………….

…………………………………[name and address of the Contractor]

Dear Sirs,

This is to notify you that your Tender dated ………………….. for execution of the …………………… …… ….. *[name of the contract and identification number, as given in the Instructions to Tenderers]* for the Contract Price of Rupees ……………………………………………………………………… ……………………………………………………………… (…………………) [amount in words and figures], as corrected and modified in accordance with the Instructions to Tenderers is hereby accepted by our Agency.

You are hereby requested to furnish Security deposit plus additional security for unbalanced tenders in terms of Clause 25.5 of ITT, in the form detailed in Clause 29.1 of ITT for an amount of Rs…….. within 20 days of the receipt of this letter of acceptance valid up to 30 days from the date of expiry of Defects Liability Period i.e. up to ……….. and sign the contract, failing which action as stated in Para 29.4 of ITT will be taken.

Yours faithfully,

Authorized Signature

Name and Title of Signatory

Name of Agency

Issue of Notice to proceed with the work

<u>(letterhead of the Employer)</u> ……………….(date)

To

………………………………….

………………………………….

…………………………………. (name and address of the Contractor)

Dear Sirs:

Pursuant to your furnishing the requisite security deposit as stipulated in ITT Clause 29.1 and signing of the contract agreement for the construction of ………………………………………… (name of the work) a Tender Price of Rs………… , you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

(Signature, name and title of signatory authorized to sign on behalf of Employer)

SECTION 5: CONDITIONS OF CONTRACT

Table of Contents

A. **General**

1. Definitions
2. Interpretation — **Page No.**
3. Law governing contract 25
4. Employers decisions 25
5. Delegation 26
6. Communications 26
7. Subcontracting 26
8. Other Contractors 26
9. Personnel 26
10. Employer's and Contractor's risks 26
11. Employer's risks 26
12. Contractor's risks 26
13. Insurance 26
14. Site Investigation Report 27
15. Query about Contract Data 27
16. Contractor to construct the Works 27
17. The Works to be completed by Intended Completion Date28 27
18. Approvals by the Employer 27
19. Safety 28
20. Discoveries 28
21. Possession of the Site 28
22. Access to the Site 28
23. Instructions 28
24. Procedure for resolution of disputes 28 28

B. **Time Control**

25. Program
26. Extension of the Intended Completion Date 29
27. Delays ordered by the Employer 29
28. Management meetings 29

C. **Quality Control** 29

29. Identifying defects
30. Tests 29
31. Correction of defects 29
32. Uncorrected defects 29

D. **Cost Control** 30

33. Bill of Quantities (BOQ)
34. Variations 30
35. Payment for Variations 30
36. Submission of bills for payment 30
37. Payments 31
38. Compensation events 31
39. Tax 31
40. Price Adjustment 31
41. Liquidated damages 32
42. Advance Payments 32
43. Securities 32
44. Cost of repairs 32

32

E **Finishing of Contract**

45. Completion
46. Taking Over 32
47. Final account 32
48. As built drawings and/or Operating and Maintenance Manuals 32
49. Termination 33
50. Payment upon termination 33
51. Property 33
52. Release from performance 34

34

F **Special Conditions of Contract**

34

3. Law governing contract

3.1 The law governing the Contract is the Laws of India supplanted by the Karnataka Local Acts.

4. Employer's decisions

4.1 Except where otherwise specifically stated, the Employer will decide contractual matters between the Employer and the Contractor.

5. Delegation

5.1 The Employer may delegate any of his duties and responsibilities to other people after notifying the Contractor and may cancel any delegation after notifying the Contractor.

6. Communications

6.1 Communications between parties which are referred to in the conditions are effective only when in writing. A notice shall be effective only when it is delivered (in terms of Indian Contract Act).

7. Subcontracting (Deleted)

7.1 Deleted.

8. Other Contractors

8.1 The Contractor shall cooperate and share the Site with other contractors, public authorities, utilities, and the Employer.

9. Personnel

9.1 The Contractor shall employ the technical personnel (of number and qualifications) as may be stipulated by GOK from time to time during the execution of the work. The technical staff so employed shall be available at site as may be stipulated by the Employer.

9.2 If the Employer asks the Contractor to remove a person who is a member of the Contractor's staff or his work force stating the reasons, the Contractor shall ensure that the person leaves the Site within seven days and has no further connection with the work in the Contract.

10. Employer's and Contractor's risks

10.1 The Employer carries the risks which this Contract states are Employer's risks, and the Contractor carries the risks which this Contract states are Contractor's risks.

11. Employer's risks

11.1 The Employer is responsible for the excepted risks which are:

(a) rebellion, riot commotion or disorder unless solely restricted to employees of the Contractor or his Sub-Contractors arising from the conduct of the Works; or

(b) a cause due solely to the design of the Works, other than the Contractor's design; or

(c) any operation of the forces of nature (in so far as it occurs on the Site) which an experienced contractor:

- (i) could not have reasonably foreseen; or
- (ii) could reasonably have foreseen, but against which he could not reasonably have taken at least one of the following measures;
  - (A) prevent loss or damage to physical property from occurring by taking appropriate measures or
  - (B) insure against such loss or damage

12. Contractor's risks

12.1 All risks of loss of or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract other than the excepted risks are the responsibility of the Contractor.

13. Insurance:

35.3 If there is no rate for the additional, substituted or altered item of the work in the BOQ, efforts would be made to derive the rates from those given in the BOQ or the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) and if found feasible the payment would be made at the derived rate for the item plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract

35.4 If the rates for additional, substituted or altered item of work cannot be determined either as at 35.1 or 35.2 or 35.3 above, the Contractor shall be requested to submit his quotation for the items supported by analysis of the rate or rates claimed, within 7 days.

35.5 If the Contractor's quotation is determined unreasonable, the Employer may order the Variation and make a change to the Contract Price which shall be based on Employer's own forecast of the effects of the Variation on the Contractor's costs.

35.6 If the Employer decides that the urgency of varying the work would prevent a quotation being given and considered without delaying the work, no quotation shall be given and the Variation shall be treated as a Compensation Event.

35.7 Under no circumstances the Contractor shall suspend the work on the plea of non-settlement of rates for items falling under this Clause.

36. Submission of bills for payment

36.1 The Contractor shall submit to the Employer monthly bills of the value of the work completed less the cumulative amount paid previously.

36.2 The Employer shall check the Contractor's bill and determine the value of the work executed which shall comprise of (i) value of the quantities of the items in the BOQ completed and (ii) valuation of Variations and Compensation Events.

36.3 The Employer may exclude any item paid in a previous bill or reduce the proportion of any item previously paid in the light of later information.

37. Payments

37.1 Payments shall be adjusted for deductions for advance payments other than recoveries in terms of contract and taxes, at source, as applicable under the law. The Employer shall pay the Contractor the within 60 days of submission of bill. The contractor shall be liable to pay liquidated damages for shortfall in progress. For progress beyond the agreed programme payment is subject to availability of the grants.

37.2 Items of the Works for which no rate or price has been entered in will not be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

38. Compensation events

38.1 The following are Compensation events unless they are caused by the Contractor:

(a) The Employer does not give access to a part of the Site by the Site Possession Date stated in the Contract Data.

(b) The Employer orders a delay or does not issue drawings, specifications or instructions required for execution of works on time.

(c) The Employer instructs the Contractor to uncover or to carry out additional tests upon work which is then found to have no Defects.

(d) The Employer gives an instruction for dealing with an unforeseen condition, caused by the Employer, or additional work required for safety or other reasons.

(e) The effect on the Contractor of any of the Employer's Risks.

(f) The Employer unreasonably delays issuing a Certificate of Completion.

(g) Other Compensation Events listed in the Contract Data or mentioned in the Contract.

38.2 If a Compensation Event would cause additional cost or would prevent the work being completed before the Intended Completion Date, the Contract Price shall be increased and/or the Intended Completion Date is extended. The Employer shall decide whether and by how much the Contract Price shall be increased and whether and by how much the Intended Completion Date shall be extended.

38.3 As soon as information demonstrating the effect of each Compensation event upon the Contractor's forecast cost has been provided by the Contractor, it is to be assessed by the Employer and the Contract Price shall be adjusted accordingly. If the Contractor's forecast is deemed unreasonable, the Employer shall adjust the Contract Price based on Employer's own forecast. The Employer will assume that the Contractor will react competently and promptly to the event.

38.4 The Contractor shall not be entitled to compensation to the extent that the Employer's interests are adversely affected by the Contractor not having given early warning or not having cooperated with the Employer.

39. Tax

39.1 The rates quoted by the Contractor shall be deemed to be exclusive of GST and inclusive of other taxes that the Contractor will have to be paid for the performance of this Contract. The Employer will perform such duties in regard to the deduction of such taxes at source as per applicable law.

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

Contractor within 90 days of receiving the Contractor's account if it is correct and complete. If it is not, the Employer shall issue within 90 days a schedule that states the scope of the corrections or additions that are necessary. If the Final Account is still unsatisfactory after it has been resubmitted, the Employer shall decide on the amount payable to the Contractor and make payment within 60 days of receiving the Contractor's revised account.

48. As built drawings and /or Operating and Maintenance Manuals

48.1 If "as built" (*Completion drawings*) Drawings and/or operating and maintenance manuals are required, the Contractor shall supply them by the dates stated in the Contract Data.

48.2 If the Contractor does not supply the Drawings by the dates stated in the Contract Data, or they do not receive the Employer's approval, the Employer shall withhold the amount stated in the Contract Data from payments due to the Contractor.

49. Termination

49.1 The Employer may terminate the Contract if the other party causes a fundamental breach of the Contract.

49.2 Fundamental breaches of Contract include, but shall not be limited to the following:

(a) The Contractor stops work for 45 days when no stoppage of work is shown on the current Program and the stoppage has not been authorized by the Employer;

(b) Deleted.

(c) The Contractor becomes bankrupt or goes into liquidation other than for a reconstruction or amalgamation;

(d) Deleted.

(e) the Employer gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Employer;

(f) The Contractor does not maintain a security which is required;

(g) the Contractor has delayed the completion of works by the number of days for which the maximum amount of liquidated damages can be paid as defined in the Contract data; and

(h) If the Contractor, in the judgment of the Employer has engaged in corrupt or fraudulent practices in competing for or in the executing the Contract.
For the purpose of this paragraph : "corrupt practice" means the offering, giving, receiving or soliciting of any thing of value to influence the action of a public official in the procurement process or in contract execution. "Fraudulent practice" means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Borrower, and includes collusive practice among Tenderers (prior to or after Tender submission) designed to establish Tender prices at artificial non-competitive levels and to deprive the Borrower of the benefits of free and open competition."

49.3 When either party to the Contract gives notice of a breach of contract to the Employer for a cause other than those listed under Sub Clause 49.2 above, the Employer shall decide whether the breach is fundamental or not.

49.4 Notwithstanding the above, the Employer may terminate the Contract for convenience.

49.5 If the Contract is terminated the Contractor shall stop work immediately, make the Site safe and secure and leave the Site as soon as reasonably possible.

50. Payment upon Termination

50.1 If the Contract is terminated because of a fundamental breach of Contract by the Contractor, the Employer shall prepare bill for the value of the work done less advance payments received up to the date of the bill, less other recoveries due in terms of the contract, less taxes due to be deducted at source as per applicable law and less the percentage to apply to the work not completed as indicated in the Contract Data. Additional Liquidated Damages shall not apply. If the total amount due to the Employer exceeds any payment due to the Contractor the difference shall be a debt payable to the Employer.

50.2 If the Contract is terminated at the Employer's convenience or because of a fundamental breach of Contract by the Employer, the Employer shall prepare bill for the value of the work done, the reasonable cost of removal of Equipment, repatriation of the Contractor's personnel employed solely on the Works, and the Contractor's costs of protecting and securing the Works and less advance payments received up to the date of the certificate, less other recoveries due in terms of the contract, and less taxes due to be deducted at source as per applicable law and make payment accordingly.

51. Property

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

51.1 All materials on the Site, Plant, Equipment, Temporary Works and Works are deemed to be the property of the Employer, if the Contract is terminated because of a Contractor's default.

52. Release from performance

52.1 If the Contract is frustrated by any event entirely outside the control of either the Employer or the Contractor the Employer shall certify that the Contract has been frustrated. The Contractor shall make the Site safe and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which commitment was made

F. Special Conditions of Contract

1. Labour:

The Contractor shall, unless otherwise provided in the Contract, make his own arrangements for the engagement of all staff and labour, local or other, and for their payment, housing, feeding and transport.

The Contractor shall, if required by the Employer, deliver to the Employer a return in detail, in such form and at such intervals as the Employer may prescribe, showing the staff and the numbers of the several classes of labour from time to time employed by the Contractor on the Site and such other information as the Employer may require.

2. Compliance with labour regulations:

During continuance of the contract, the Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the State or Central Government or local authority and any other labour law (including rules), regulations, bye laws that may be passed or notification that may be issued under any labour law in future either by the State or the Central Government or the local authority. The Contractor shall keep the Employer indemnified in case any action is taken against the Employer by the competent authority on account of contravention of any of the provisions of any Act or rules made there under, regulations or notifications including amendments. If the Employer is caused to pay or reimburse, such amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated in the notifications/bye laws/Acts/Rules/regulations including amendments, if any, on the part of the Contractor, Employer shall have the right to deduct any money due to the Contractor including his amount of security deposit. The Employer shall also have right to recover from the Contractor any sum required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor in no case shall be treated as the employees of the Employer at any point of time

3. Protection of Environment:

The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor shall abide at all times by all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.

4. Arbitration (Clause 24)

4.1 The procedure for arbitration shall be as follows:

(a) In case of dispute or difference arising between the Employer and the Contractor relating to any matter arising out of or connected with this agreement it shall be settled in accordance with the Arbitration and Conciliation Act 1996. The disputes or differences shall be referred to a Sole Arbitrator. The Sole Arbitrator shall be appointed by agreement between the parties; failing such agreement, by the Appointing Authority (any one of the Organizations as per list enclosed in Annexure)

(b) Arbitration proceedings shall be held at.. Karnataka state (to be filled in by the Employer before issue of the Tender Documents).

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

(c) The cost and expenses of arbitration proceedings will be paid as determined by the Arbitrator. However the expenses incurred by each party in connection with the preparation, presentation, etc., shall be borne by each party itself.

5. In the case of the death of a Contractor after executing the agreement / commencement of the work, his legal heir, if an eligible registered Contractor and willing can execute and complete the work at the accepted tender rates irrespective of the cost of the work.
6. The Contractor should produce invoice for procurement of Bitumen, Steel, HDPE ducts, Geo-textile material along with bills. No payments will be made without such invoices.
7. Mix Designs for Concrete and Asphalt work should be got approved by Chief Engineer before commencement of Work.
8. 63/51 mm Double Walled Corrugated HDPE Duct should have the inner layer as silicore marking the duct manufacturer and also size of the duct. The Duct should conform to ISO Certification and the colour of duct should be orange or blue for better identity.
9. The Contractor shall provide One four wheeler along with driver, fuel expenses to Project Engineers in-charge of work to facilitate and co-ordinate the supervision of the work.
10. The Contractor shall establish field lab and field office to facilitate quality assurance of execution of works.
11. The hot mix plant unit should be within the radius of 40km from Vidhanasoudha, Bangalore
12. The availability of hot mix plant and ownership will be ascertained by physical inspection at the time of technical evaluation by the evaluation authority
13. GST Shall be Paid to the Tendered Amount Separately
14. Tenderer should have Registered with EPF and ESI authorities: Certification should be produced at the time of Tendering OR else being entering into the Agreement.

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

Milestone 1 i.e Financial Progress for Rs.0.82 Crores within 03 Months from the date of work order (33%)
Milestone 2 i.e Financial Progress for Rs.1.64 Crores within 06 Months from the date of work order (66%)

Milestone 3 i.e Financial Progress for Rs.2.49 Crores within 09 Months from the date of work order (100%)

The Site Possession Date is:[13] **Date of work order** [21]

The Site is located at **Yelahanka Division Limits** and is defined in drawings [1.1]

The Defects Liability Period is **3 Years** for roads asphalted with both BM/DBM and BC [14]. [31]
The Defects Liability Period is **1 Year** for roads asphalted with only BC [15].
The Defects Liability Period is **1 Year** for civil works

Insurance requirements are as under: [13]

	Type of Cover	Minimum cover for Insurance[16]
(i)	Works of Plant and materials	The sum stated in the Agreement plus 20%
(ii)	Loss or damage to equipment	Full replacement cost
(iii)	Loss or damage to property of Third Party	Full replacement cost
(iv)	Personal injury or death insurance (a) for Third Party[17]	
	(b) for Contractor's employees or labour	In accordance with the statutory requirements applicable to Karnataka

Price Adjustment Formula;[18]

[40]

R= Value of work as defined in Clause 40.1 of Conditions of Contract.

Adjustment for labour component:

(i) Price adjustment for increase or decrease in the cost due to labour shall be paid in accordance with the following formula:

$V_L = 0.85 \times P_L / 100 \times R \times (L_i - L_o) / L_o$ Where,

V_L = Increase or decrease in the cost of work during the quarter under consideration due to changes in rates for local labour;
L_o = The average consumer price index[19] for industrial workers for Bangalore Centre for the quarter preceding the date of opening of tenders as published by the Labour Bureau, Ministry of Labour, Government of India;

---

[13] At the time of preparation of the tender document give the period after the issue of work order, when the site would be made available to the contractor, for example 'one week after the issue of work order'
[14] The period should depend up on the period required for testing of the work. In case of building it could be 12 months (passing of one rainy season); for pipe laying work, tanks, water retaining structures, the time required for testing; for canals, lining works, the passing of one monsoon or running of canal whichever is lower; roads and highways passing of one monsoon (12 months)
[15] The period should depend up on the period required for testing of the work. In case of building it could be 12 months (passing of one rainy season); for pipe laying work, tanks, water retaining structures, the time required for testing; for canals, lining works, the passing of one monsoon or running of canal whichever is lower; roads and highways passing of one monsoon (12 months)
[16] Employer to specify as per requirement. Exclusions if any should also be specified.
[17] Specify an appropriate figure. For normal works it could be Rs.20 lakhs to cover 4 persons @Rs.5 lakhs each.
[18] The Formula has some normal components. It should be changed if need be to suit the nature of the work.
[19] The Index numbers are available in the web site *http://labourbureau.nic.in/indtab.html*

YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

Adjustment of Fuel and Lubricant component:

(v) Price adjustment for increase or decrease in cost of Fuel and Lubricants shall be paid in accordance with the following formula:

$$V_F = 0.85 \times P_F/100 \times R \times (F_i - F_o)/F_o, \text{ Where,}$$

V_F = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for Fuel and Lubricants.

F_o = The official retail price of High Speed Diesel (HSD) at the IOC/HPCL/BPL or other consumer pump at Bangalore on the day 30 days prior to the date of opening of Bids.

F_i = The official retail price of HSD at the IOC/HPCL/BPL or other consumer pump at Bangalore for the 15th day of the middle calendar month of the quarter under consideration.

P_F = Percentage of Fuel and Lubricant component of the work.

Note: For the application of this Clause the price of HSD[24] has been chosen to represent Fuel and Lubricant Group

Adjustment for Plant and Machinery Spares Component:

(vi) Price adjustment for increase or decrease in the cost of plant and machinery spares procured by the contractor shall be paid in accordance with the following formula:

$$V_P = 0.85 \times P_P/100 \times R \times (P_i - P_o)/P_o, \text{ Where}$$

V_P = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for plant and machinery spares.

P_o = The all India average wholesale price index for Heavy machinery and parts for the quarter preceding the date of opening of bids, as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

P_i = The all India average wholesale price index for Heavy machinery and parts for the quarter under consideration as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

P_B = Percentage of Plant and Machinery Spares component of the work.

Note: For the application of this Clause index of Heavy Machinery and Parts[25] has been chosen to represent the Plant and Machinery Spares Group.

Adjustment for Other materials.:

(vii) Price adjustment for increase or decrease in the cost of other materials other than cement, steel, bitumen and Fuel and Lubricants[26], procured by the contractor shall be paid in accordance with the following formula:

$$V_M = 0.85 \times P_M/100 \times R \times (M_i - M_o)/M_o, \text{ Where}$$

V_M = Increase or decrease in the cost of work during the quarter under consideration due to changes in the rates for local materials other than cement, steel, bitumen and Fuel and Lubricants.

M_o = The all India average wholesale price index for all commodities for the quarter preceding the date of opening of bids, as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

M_i = The all India average wholesale price index for all commodities for the quarter under consideration as published by the Office of the Economic Advisor, Ministry of Commerce and Industry, Government of India, New Delhi

P_M = Percentage of other material component (Other than cement, steel, bitumen and Fuel and Lubricants) of the work.

The following percentages [27] will govern the price adjustment for the entire contract:[28]

---

[24] This could be appropriately changed to any other item depending on the nature of work.

[25] This could be appropriately changed to any other item depending on the nature of the work.

[26] Add, delete or change depending on the nature of work.

The amount to be withheld for failing to supply "as built" drawings or supply of Operation and Maintenance Manuals by the date required is **Rs 1,00,000/-**

(The amount should be sufficient to get the completion drawings or Operating and Maintenance Manuals prepared by alternative agency in case the contractor fails to submit.) [48]

The following events shall also be fundamental breach of the contract: [49.2]

1. The contractor has contravened Sub-clause 7.1 and Clause 9 of CC.

The percentage to apply to the value of the work not completed representing the Employer's Additional cost for completing the Works shall be <u>30</u> percent (30%) . [50.1]

(Change if need be. It should be sufficient to get the balance of works completed by alternative agency.)

SECTION 7: SPECIFICATIONS

As per specifications mentioned in BOQ

SECTION 8: DRAWINGS

(Enclosed)

SECTION 9: BILL OF QUANTITIES

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:-CONSTRUCTION OF ADDITIONAL CLASS ROOMS AND COMPOUND WALL AT GOVT HIGHER PRIMARY SCHOOL(BANGLA SCHOOL)AT YELAHANKA OLD TOWN IN KEMPEGOWDA WARD NO.01

SCHEDULE-B

Item No	Description of Work	Unit	Total Quantity	Rate as per estimate in Rs.	
				In Figures	In Words
1	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. C. Prestressed / Reinforced cement concrete grade M-20 & above. Complete as per specifications and the directions of the Engineer-in-charge	cum	55.40		
2	Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications Dismantling brick/Tile work Complete as per specifications and the directions of the Engineer-in-charge	Cum	129.20		
3	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms)Complete as per specifications and the directions of the Engineer-in-charge	Sqm	214.24		
4	.Dismantling plastering and removing the debris with a lead upto 200m.Complete as per specifications and the directions of the Engineer-in-charge	Sqm	616.57		

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

5	Earth work for lowering and levelling the ground other than foundation works by mechanical means upto 3.00 depth, including providing shoring and strutting, removal of stumps and other deleterious matter, dressing of sides and bottom, filling back the excavation earth to the extent required including the cost of labour & HOM of machineries, Complete as per specifications and the directions of the Engineer-in-charge	Cum	59.13		
6	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., complete as per the direction of the Engineer-in-charge.	Cum	288.20		
7	Removing and Reinstalation of RO Plant(Data rate)	No	1.00		
8	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the exavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods Complete as per specifications and the directions of the Engineer-in-charge	Cum	615.91		
9	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. Complete as per specifications and the directions of the Engineer-in-charge	Cum	69.28		
10	Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing Complete as per specifications and the directions of the Engineer-in-charge	Cum	65.91		
11	Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing Complete as per specifications and the directions of the Engineer-in-charge	Cum	108.96		
12	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerddressed in courses not less than 20 cms high, bond stones at 2m apart in each course including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Cum	92.97		
13	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour Complete as per specifications and the directions of the Engineer-in-charge	Cum	118.51		
14	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., complete as per the direction of the Engineer-in-charge.Complete as per specifications and the directions of the Engineer-in-charge	Cum	497.40		

15	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	315.19			
16	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness , including attached pilasters, buttresses, plinth and string courses cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	309.89			
17	Providing and removing centering, shuttering, strutting, propping etc. and Removal of form Work for columns, pillars, piers, post and struts, square / rectangular / polygon in plan including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	324.89			
18	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons for heights more than 3.50m from ground level. - 0 to 5 mtrs.Complete as per specifications and the directions of the Engineer-in-charge	Sqm	1140.61			
19	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labourComplete as per specifications and the directions of the Engineer-in-charge	Sqm	50.91			
20	:Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	520.64			
21	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	65.36			
22	:Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc. , including edges including cost of all materials, labourComplete as per specifications and the directions of the Engineer-in-charge	Sqm	48.30			
23	Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0 70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, Complete as per specifications and the directions of the Engineer-in-charge	Cum	252.54			

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIVISION

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

29	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	18.36			
30	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	1.08			
31	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specifications and the directions of the Engineer-in-charge	tonne	54.60			
32	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specifications and the directions of the Engineer-in-charge First Floor	tonne	20.84			
33	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specifications and the directions of the Engineer-in-charge Second Floor	tonne	1.68			
34	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., Complete as per specifications and the directions of the Engineer-in-charge	Sqm	506.28			

CONTRACTOR

EXECUTIVE ENGINEER
Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

35	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	484.71		
36	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	61.71		
37	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc., Complete as per specifications and the directions of the Engineer-in-charge	Sqm	201.84		
38	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc., Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	237.54		
39	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc., Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	117.60		
40	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Sqm	756.14		
41	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	807.69		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIVN

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

	...rendering, Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	309.99		
43	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Sqm	744.10		
44	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	694.34		
45	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	70.14		
46	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Sqm	115.71		
47	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	111.09		
48	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to ceiling including rounding off corners wherever required smooth rendering, : including Providing and removing scaffolding, including cost of materials, labour, curingComplete as per specifications and the directions of the Engineer-in-charge	Sqm	508.29		
49	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to ceiling including rounding off corners wherever required smooth rendering, : including Providing and removing scaffolding, including cost of materials, labour, curingComplete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	510.24		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka Division

50	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to ceiling including rounding off corners wherever required smooth rendering, : including Providing and removing scaffolding, including cost of materials, labour, curingComplete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	25.90		
51	providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty . Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of alll mateerial cost of labour and scaffolding etc. ,Complete as per specifications and the directions of the Engineer-in-charge	Sqm	2553.01		
52	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour,Complete as per specifications and the directions of the Engineer-in-charge	Sqm	1508.58		
53	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications page no117 item no 15.49.1 . KSRB 15-14.1 : Extra over Item 15-14.1 for applying oil bound washable distemper on ceiling and / or sloping roof Complete as per specifications and the directions of the Engineer-in-charge	Sqm	1044.43		
54	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, Complete as per specifications and the directions of the Engineer-in-charge	Sqm	774.50		
55	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	826.05		
56	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	311.07		

Executive Engineer
Bruhat Bengaluru Mahanagara Palike

	mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials,mortar,labour,curing etc.,Complete as per specifications and the directions of the Engineer-in-charge	Sqm	61.02			
58	Providing and laying Hassan Green / River Pink granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials,mortar,labour,curing etc.,Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	61.02			
59	Providing and laying M-15 cement concrete flooring, 50 mm thick with metallic concrete hardner topping , under layer of 35mm thick m-15 cement concrete using broken granite metal of 20mm and down size, and top layer 50mm thick of metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with which metallic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement and 1 part of metallic floor hardening compound of approved quality by wt) , including finishing cost of materials, labour, curing, Complete as per specifications and the directions of the Engineer-in-charge	Sqm	508.29			
60	Providing and laying M-15 cement concrete flooring, 50 mm thick with metallic concrete hardner topping , under layer of 35mm thick m-15 cement concrete using broken granite metal of 20mm and down size, and top layer 50mm thick of metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with which metallic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement and 1 part of metallic floor hardening compound of approved quality by wt) , including finishing cost of materials, labour, curing, Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	510.24			
61	Providing and laying M-15 cement concrete flooring, 50 mm thick with metallic concrete hardner topping , under layer of 35mm thick m-15 cement concrete using broken granite metal of 20mm and down size, and top layer 50mm thick of metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with which metallic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement and 1 part of metallic floor hardening compound of approved quality by wt) , including finishing cost of materials, labour, curing, Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	25.90			

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

62	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mmComplete as per specifications and the directions of the Engineer-in-charge	Sqm	481.73		
63	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mmComplete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	483.33		
64	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mmComplete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	25.90		
65	Providing skirting, dado, rises of steps with colour glazed tiles 30X60 cms 6mm thick with border of size 30 x 10 cms on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications and the directions of the Engineer-in-charge	Sqm	115.71		
66	Providing skirting, dado, rises of steps with colour glazed tiles 30X60 cms 6mm thick with border of size 30 x 10 cms on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	111.09		
67	Providing Ceramic tiles of size 30x30cms 6mm thick of approved make ,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, Complete as per specifications and the directions of the Engineer-in-charge	Sqm	29.76		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

68	Providing Ceramic tiles of size 30x30cms 6mm thick of approved make ,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	30.10			
69	Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs. (c) After two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 300x300mm square. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test including cost of materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Cum	571.45			
70	Fixing of door frames in an existing opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, Complete as per specifications and the directions of the Engineer-in-charge	Nos	17.00			
71	Providing Honne wood frames of doors, windows, clerestory windows,ventilators and other frames , wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps),but including cost of materials, labour, HOM of machineries Complete as per specifications and the directions of the Engineer-in-charge	Cum	1.97			
72	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per specifications and the directions of the Engineer-in-charge	Sqm	21.42			
73	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	17.64			

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

74	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	1.89	
75	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour,Complete as per specifications and the directions of the Engineer-in-charge	Sqm	43.34	
76	Providing and fixing 65mmx90mm GRP Doorframe fabricated using E-Glass Chopped Strand Mat (CSM). U.V-stabilized Isopthalic Gelcoat and Isopthalic resin. The thickness of the GRP skin shall not be less than 2.0 mm. The doorframe consists of four segmens, which are provided with plug-in-socket arrangement in-situ in the mould. The segments are plugged in and are joined together by means of screws. The GRP frame shall be provided with wooden reinforcement of 6 locations fro high screw holding capacity for fixing metallic hold fast and shall be consolidated by filling with medium density foam/Plaster with fibre reinforcement. Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat hold fast shall be provided with the frame. Complete as per specifications and the directions of the Engineer-in-charge	m	28.50	
77	Providing and fixing 65mmx90mm GRP Doorframe fabricated using E-Glass Chopped Strand Mat (CSM). U.V-stabilized Isopthalic Gelcoat and Isopthalic resin. The thickness of the GRP skin shall not be less than 2.0 mm. The doorframe consists of four segmens, which are provided with plug-in-socket arrangement in-situ in the mould. The segments are plugged in and are joined together by means of screws. The GRP frame shall be provided with wooden reinforcement of 6 locations fro high screw holding capacity for fixing metallic hold fast and shall be consolidated by filling with medium density foam/Plaster with fibre reinforcement. Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat hold fast shall be provided with the frame. Complete as per specifications and the directions of the Engineer-in-charge First Floor	m	45.60	
78	Providing and fixing 65mmx90mm GRP Doorframe fabricated using E-Glass Chopped Strand Mat (CSM). U.V-stabilized Isopthalic Gelcoat and Isopthalic resin. The thickness of the GRP skin shall not be less than 2.0 mm. The doorframe consists of four segmens, which are provided with plug-in-socket arrangement in-situ in the mould. The segments are plugged in and are joined together by means of screws. The GRP frame shall be provided with wooden reinforcement of 6 locations fro high screw holding capacity for fixing metallic hold fast and shall be consolidated by filling with medium density foam/Plaster with fibre reinforcement. Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat hold fast shall be provided with the frame. Complete as per specifications and the directions of the Engineer-in-charge Second Floor	m	5.70	

79	Providing and fixing factory made single leaf rigid GRP Sandwich composite door shutter of 40 mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and one layer of 450 gns E-Glass Chopped Strand Mat (CSM), impregnated with orthopthalic polyester resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 37mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not lessthan 36mmx32mmand also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc. shall be provided. A structural adhesive compatible with EPS foam shall be used for bonding the core material, the salwood reinforement and the skins. The material and process for manufacturing the door shutters shall confirm to RV-TIFAC Composites Design Centre Standards and specifications and the door shutters tested in confiramation to IS 4020-1994. The finish of shutter will be plain coulur White/IVORY/Beige/Light Grey or any other colour using high quality pigments. Excluding cost of fixtures and inclusive of supply of shutters to respective work spot.Complete as per specifications and the directions of the Engineer-in-charge	Sqm	7.88			
80	Providing and fixing factory made single leaf rigid GRP Sandwich composite door shutter of 40 mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized Isopthalic Gelcoat and one layer of 450 gns E-Glass Chopped Strand Mat (CSM), impregnated with orthopthalic polyester resin. The thickness of the skins shall not be less than 1.5mm. Expanded Polystyrene (EPS) structural foam panel of 37mm thickness and a density of 20 Kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Salwood block of cross section not lessthan 36mmx32mmand also necessary salwood reinforcements for fixing the metal fittings such as tower bolts, aldrops, handles, etc. shall be provided. A structural adhesive compatible with EPS foam shall be used for bonding the core material, the salwood reinforement and the skins. The material and process for manufacturing the door shutters shall confirm to RV-TIFAC Composites Design Centre Standards and specifications and the door shutters tested in confiramation to IS 4020-1994. The finish of shutter will be plain coulur White/IVORY/Beige/Light Grey or any other colour using high quality pigments. Excluding cost of fixtures and inclusive of supply of shutters to respective work spot.Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	12.60			
81	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a minimum of 60- 70 microns with exterior durable pure polyester grade powder of approved quality.Complete as per specifications and the directions of the Engineer-in-charge	Sqm	48.60			

82	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a minimum of 60- 70 microns with exterior durable pure polyester grade powder of approved quality.Complete as per specifications and the directions of the Engineer-in-charge First floor	Sqm	49.95		
83	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - using aluminium section powdered coated to a minimum of 60- 70 microns with exterior durable pure polyester grade powder of approved quality.Complete as per specifications and the directions of the Engineer-in-charge Second Floor	Sqm	1.80		
84	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery Complete as per specifications and the directions of the Engineer-in-charge	kg	1020.60		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Division

85	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery Complete as per specifications and the directions of the Engineer-in-charge First Floor	kg	1048.95			
86	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery Complete as per specifications and the directions of the Engineer-in-charge Head Room	kg	35.66			
87	Providing and fixing M.S.Grill over existing compound wall as per, using 16mm x 16mm M.S.Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., Complete as per specifications and the directions of the Engineer-in-charge	Sqm	62.10			
88	Providing and fixing M.S.Grill over existing compound wall as per, using 16mm x 16mm M.S.Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., Complete as per specifications and the directions of the Engineer-in-charge First floor	Sqm	71.30			
89	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, Complete as per specifications and the directions of the Engineer-in-charge	sqm	334.10			
90	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications (Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) Complete as per specifications and the directions of the Engineer-in-charge	cum	426.84			

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike

91	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., Complete as per specifications and the directions of the Engineer-in-charge	Sqm	18.81		
92	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., Complete as per specifications and the directions of the Engineer-in-charge First Floor	Sqm	18.81		
93	Providing 20mm square M.S footrest and fixing in manhole Nos 232.00 with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curingComplete as per specifications and the directions of the Engineer-in-charge	No.s	4.00		
94	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all Complete as per specifications and the directions of the Engineer-in-charge	Sqm	52.94		
95	Providing and fixing white vitreous china clay,flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C I / M.S brackets ,32mm C.P brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Unit	6.00		

CONTRACTOR

EXECUTIVE ENGINEER

Executive Engineer

96	Providing and fixing white vitreous china clay, water closet europeon type (pedestal type, p-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level,P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets , 40mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design,painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Each	13.00		
97	Providing and fixing white vitreous china clay,flat back or half stall urinal basin of size 580x380x350mm in the range of two with 7.5 litres P.V.C automatic flushing cistern, C.I / M.S brackets ,standard flush pipe and C.P brass spreaders with brass unions and G.I clamps, C.I trap with outlet grating and other couplings in C.P brass, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Unit	4.00		
98	Providing and fixing 453x357mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Unit	6.00		
99	Providing and fixing C.P brass towel rail 740mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P brass screws including cost of materials, labourComplete as per specifications and the directions of the Engineer-in-charge	Unit	12		
100	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. Complete as per specifications and the directions of the Engineer-in-charge	Each	30.00		
101	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications.For Rain water pipe. Complete as per specifications and the directions of the Engineer-in-charge	m	90.00		
102	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications For Rain water pipe. Complete as per specifications and the directions of the Engineer-in-charge	m	100.00		

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

103	Constructing brick masonry inspection chamber 600x600mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 600x600mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 600x600mm. Complete as per specifications and the directions of the Engineer-in-charge	Nos.	8.00		
104	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing Complete as per specifications and the directions of the Engineer-in-charge	Each	2.00		
105	Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads Complete as per specifications and the directions of the Engineer-in-charge	Each	25.00		
106	Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leadsComplete as per specifications and the directions of the Engineer-in-charge	Each	20.00		
107	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads Complete as per specifications and the directions of the Engineer-in-charge	Each	4.00		
108	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,) Complete as per specifications and the directions of the Engineer-in-charge **20mm nominal OD pipes**	m	80.00		

109	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,)Complete as per specifications and the directions of the Engineer-in-charge **25mm nominal OD pipes**	m	90.00			
110	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Netural) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper confirming to the GTP With a 6Amps flusg type SP control switch shall be fixed on the existing plastic sheet / gand box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block, Complete as per specifications and the directions of the Engineer-in-charge i. **Short point upto 3m**	Point	250.00			
111	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Netural) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper confirming to the GTP With a 6Amps flusg type SP control switch shall be fixed on the existing plastic sheet / gand box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block,Complete as per specifications and the directions of the Engineer-in-charge . **Medium point above 3m - 6m**	Point	175.00			
112	Concealed Conduit System - Supplying heavy gague PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, adhesive paste etc, and running before concreting and slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fisg wire wherever necessary **19/20mm dia, 2mm thick** Complete as per specifications and the directions of the Engineer-in-charge	Rm	800.00			
113	Concealed Conduit System - Supplying heavy gague PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, adhesive paste etc, and running before concreting and slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fisg wire wherever necessary **25mm dia, 2mm thick** Complete as per specifications and the directions of the Engineer-in-charge	Rm	1400.00			

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Yelahanka, Division

114	Concealed Conduit System - Supplying heavy gague PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, adhesive paste etc, and running before concreting and slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fisg wire wherever necessary **32mm dia, 2mm thick** Complete as per specifications and the directions of the Engineer-in-charge	Rm	300.00		
115	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary. **19/20mm dia, 2mm thick** Complete as per specifications and the directions of the Engineer-in-charge	Mtr	250.00		
116	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary. **25mm dia, 2mm thick** Complete as per specifications and the directions of the Engineer-in-charge	Mtr	800.00		
117	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary.**32mm dia, 2mm thick** Complete as per specifications and the directions of the Engineer-in-charge	Mtr	450.00		
118	Supplying and flush modular poweder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall **1 - 3 Way** Complete as per specifications and the directions of the Engineer-in-charge	Each	200.00		
119	Supplying and flush modular poweder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall **4 - 5 Way** Complete as per specifications and the directions of the Engineer-in-charge	Each	175.00		

CONTRACTOR

EXECUTIVE ENGINEER

Executive Engineer

Mahanagara Palike

120	Supplying 6A flush type socket and 6 amp flush type SP switch either surface/flush mountinh in existing gang box or in 4mm thik plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wire as required as per IS 1293 and IS 3654 . **6AMP 3/5 and Switch** Complete as per specifications and the directions of the Engineer-in-charge	Each	250.00		
121	Supplying and mounting 2 Nos, of 2 Way 6amps flush type switches either surface/flush mounted on existing gang box or in 4mm thick plastic sheet and mounted on a flusg mounted wooden box and wiring as per IS 1293 Complete as per specifications and the directions of the Engineer-in-charge	Each	100.00		
122	Supply and fixing of bakelite D.P /socket/switch with/ without neon indicator over existing wood board or flush mounting in plastic plates/nitches as per IS 1293 and IS 3854 **16Amps Combined switch and socket with indication** Complete as per specifications and the directions of the Engineer-in-charge	No	75.00		
123	Electronic stepped regulator. Complete as per specifications and the directions of the Engineer-in-charge	No	166.00		
124	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements. **1.5sqmm** Complete as per specifications and the directions of the Engineer-in-charge	Rm	625.00		
125	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements. **2.5sqmm** Complete as per specifications and the directions of the Engineer-in-charge	Rm	1600.00		
126	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements. **4sqmm** Complete as per specifications and the directions of the Engineer-in-charge	Rm	950.00		
127	Supplying and fixing Metal Fan Box with Round Hook Complete as per specifications and the directions of the Engineer-in-charge	Nos	166.00		

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

128	Supplying and fixing of Group A, regular MCB distribution boards on wall/woodboard/flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB'S single phase/ 3 phase / single door with powder coated painting made out of SWG MS enclosute **12 way SP & N** Complete as per specifications and the directions of the Engineer-in-charge	Nos	30.00		
129	Supply and fixing miniature circuit breakers on the existing MCB distribution boards using necessary fixing meterials and "C" type curve, Indiator ON/OFF energy cross -3 with as required confirming to IEC 60898 **5-32 AMPS DP** Complete as per specifications and the directions of the Engineer-in-charge	Nos	15.00		
130	Supplying, fixing and wiring earth electrode for grounding conduits , I.C. cutouts and others equipments on the meter board using 40mm dia 2.90mm long buried in a pit.. the pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit ect, is to be established through GI wire of size as ISI specification 7.3.3 of IS 732 using 12mm dia bolt, nut, washers and check nuts ect... the pipe shall have 16 through holes of 122mm dia, Complete as per specifications and the directions of the Engineer-in-charge	No	2.00		
131	Supplying and running of GI/ copper strips for grounding connections, using necessary fixing materials as required. **25 x 3mm G.I strip** Complete as per specifications and the directions of the Engineer-in-charge	Mtr	80.00		
132	Supplying of ......feet - PVC Batten with integrated LED tube .....W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50/60Hz & Power factor >0.9 along with CE approved. 2 years Warranty against any manufacturing defect working under standard electrical condition. LED light fighting 1 x4'-20/22 w Complete as per specifications and the directions of the Engineer-in-charge	Each	350.00		
133	upplying & fixing retrofit type -PL- LED Lamp ....W LED linear source with CCT 6500 degree K, CRI> 70%. efficacy >80 lumen per watt, life> 25000 burning hours and Compliance to IS 10322/IEC 60598, LM 79 & LM 80. The LED are driven by HF electronic driver integrated in the system, with PF > 0.95, power loss should < 5% of lamp wattage., short circuit & open circuit protection to be integrated in the circuit, THD less than 20%, Life as per LM 79. The operating input voltage should be between 130 to 275 volts. Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition. **8-9 Watts** Complete as per specifications and the directions of the Engineer-in-charge	Each	100.00		
134	Supplying capacitor type ceiling fan complete with down rod blades shackle, canopies etc, for operation on 230 volts, 50 cycles. single phase AC supply conforming to ISS-374-1979 and with double ball bearing system 48" sweep (1200mm) Complete as per specifications and the directions of the	Each	166.00		

CONTRACTOR

EXECUTIVE ENGINEER

Executive Engineer
Bruhat Bengaluru Mahanagara Palike

135	Supply Exhaust fan if 1440 RPM of (12") size with dracket blades complete for light duty suitable to -oerate on 230V 50Hz, supply Complete as per specifications and the directions of the Engineer-in-charge	Each	35.00			
136	Supplying and fixing Trivector meter suitable for operation LT operation and CT operated meter in polycarbonate body in class 0.5accuracy as per IS 14697 and completely wired Complete as per specifications and the directions of the Engineer-in-charge	Each	2.00			
137	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C. 50 Hz 12/24v D.C (48/6.36) Complete as per specifications and the directions of the Engineer-in-charge	Each	2.00			
138	Supplying, fixing and wiring 50/5 to 1000/5Amps 5VA burden Current Transformer. Class 0.5 accuracy with Tape Wound (48/6.32) Complete as per specifications and the directions of the Engineer-in-charge	Each	2.00			
139	Supplying of 1.1 KV LT UG cable having aluminium conductor PVC insulated, extruded inner sheathed, galvanised, steel strip (except 2Cx 10Sq.mm wire armoured) Confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheated armoured cable with specified IS-1554 Part-1:1998 & confirming to the attached GTP of GROUP-A. (62/7.4) 3.5 core 240 sqmm Complete as per specifications and the directions of the Engineer-in-charge	Mtr	50.00			
140	Supplying of 1.1 KV LT UG cable having aluminium conductor PVC insulated, extruded inner sheathed, galvanised, steel strip (except 2Cx 10Sq.mm wire armoured) Confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheated armoured cable with specified IS-1554 Part-1:1998 & confirming to the attached GTP of GROUP-A. (62/7.4) 3.5 core 25 sqmm Complete as per specifications and the directions of the Engineer-in-charge	Mtr	20.00			
141	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct. (68/7.8) 25 sqmm to 75 sqmm Complete as per specifications and the directions of the Engineer-in-charge	Mtr	20.00			
142	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct. (68/7.8) 300 sqmm 400 Sqmm Complete as per specifications and the directions of the Engineer-in-charge	Mtr	50.00			
143	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.(64/7.21) 25 sqmm to 75 sqmm Complete as per specifications and the directions of the Engineer-in-charge	Each	4.00			

CONTRACTOR

EXECUTIVE ENGINEER
YELAHANKA DIV

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

144	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.(64/7.21) 300 sqmm 400 Sqmm Complete as per specifications and the directions of the Engineer-in-charge	Each	4.00		
145	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only) (69/7.14) 50mm dia Complete as per specifications and the directions of the Engineer-in-charge	Each	4.00		
146	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only) (69/7.14) 70mm dia Complete as per specifications and the directions of the Engineer-in-charge	Each	4.00		
147	Digging of trench of 0.6m deep x 0.50 mtr wide refiling the trench to the required ground level and consolidating. (68/7.9) In Hard Soil Complete as per specifications and the directions of the Engineer-in-charge	Mtr	50.00		
148	Supplying and fixing of class A (medium duty) GI pipe of wall thick ness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class. (68/7.12) 40mm Complete as per specifications and the directions of the Engineer-in-charge	Mtr	30.00		
149	Supplying and fixing of class A (medium duty) GI pipe of wall thick ness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class. (68/7.12) 65mm Complete as per specifications and the directions of the Engineer-in-charge	Mtr	30.00		

(1) Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities (refer: ITB Clause 11.2 and CC Clause 37.2).
(2) Unit rates and prices shall be quoted by the Tenderer in Indian Rupees.
(3) Where there is a discrepancy between the rate in figures and words, the lower of the two will govern.
(4) Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity, the unit rate quoted shall govern [ITT Clause 24.1 (b)]
(5) GST will be paid separately to the Tendered Amount

SECTION 10: FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT

To: .... *[name of Employer]*
.... *[address of Employer]*

WHEREAS .... *[name and address of Contractor]* (hereinafter called "the Contractor") has undertaken, in pursuance of Contract No. .... dated : .... to execute ....*[name of Contract and brief description of Works]* (hereinafter called "the Contract");

AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with a Bank Guarantee by a recognized bank for the sum specified therein as security for compliance with his obligations in accordance with the Contract;

AND WHEREAS we have agreed to give the Contractor such a Bank Guarantee;

Executive Engineer

NOW THEREFORE we hereby affirm that we are the Guarantor and responsible to you, on behalf of the Contractor, up to a total of Rs. .... *[amount of guarantee]* Rupees...*[in words]*, and we undertake to pay you, upon your first written demand and without cavil or argument, any sum or sums within the limits of .... *[amount of guarantee]*[39] as aforesaid without your needing to prove or to show grounds or reasons for your demand for the sum specified therein.

We hereby waive the necessity of your demanding the said debt from the Contractor before presenting us with the demand.

We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.

This guarantee shall be valid until 30 days from the date of expiry of the Defects Liability Period.

Signature and seal of the guarantor ____________________
Name of Bank ____________________
Address ____________________
Date ____________________

[38] An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract

[39] An amount shall be inserted by the Guarantor, representing the percentage of the Contract Price specified in the Contract

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division